

**ANNEX B****Bidding Form No. 5****RENOVATION OF DFPC PROVINCIAL STORE OUTLETS - LOT 2 ILOILO  
BILL OF MATERIALS****1. PAINTING WORKS :(CEILING &WALL ); ( HANGING CABINET & TABLE )**

| Material Description            | Qty.   | U - Cost | Amount      |
|---------------------------------|--------|----------|-------------|
| Perma Coat Flat Latex (white )  | 7 Tins |          |             |
| Perma Coat Gloss Latex (white ) | 4 Tins |          |             |
| Gypsum Putty                    | 2 Tins |          |             |
| Lacquer high gloss Enamel       | 3 gal  |          |             |
| Lacquer Thinner                 | 8 gal  |          |             |
| Lacquer Putty                   | 2 gal  |          |             |
| Lacquer Flo                     | 1 gal  |          |             |
| Boral                           | 1 bag  |          |             |
| Roller Brush / w/ tray          | 3 pcs  |          |             |
| Paint Brush                     | 4 pcs  |          |             |
| Polytuff                        | 3 Gal  |          |             |
| Sanding Paper #360              | 50 pcs |          |             |
| Sanding Paper #100              | 50 LM  |          |             |
| Sanding Paper #80               | 5 LM   |          |             |
| Rug (cotton )                   | 6 kls  |          |             |
| Consumables                     | 1 lot  |          |             |
| <b>Total Amount :</b>           |        |          | <b>0.00</b> |

**2. FLOORING**

| Material Description                      | QTY.   | U - Cost | Amount        |
|---|--------|----------|---------------|
| 3mm x 450mm x 450mm Alabaster Vinyl tiles | 60 pcs |          |               |
| Power Bond Adhesive                       | 1 Gal  |          |               |
| <b>Total Amount :</b>                     |        |          | <b>P 0.00</b> |

**3. TEMPORARY ENCLOSURE**

| Material Description           | QTY.    | U - Cost | Amount        |
|--------------------------------|---------|----------|---------------|
| ¼"thk 4' x 8' ordinary plywood | 15 pcs  |          |               |
| 2" x 3" x 10' metal stud       | 35 pcs  |          |               |
| 1½" black screw                | 400 pcs |          |               |
| Cylindrical door knob          | 1 set   |          |               |
| 3" x 3" loosepin hinges        | 2 pcs   |          |               |
| Flat latex (white)             | 2 gal   |          |               |
| masking tape 1"                | 3 rolls |          |               |
| <b>Total Amount :</b>          |         |          | <b>P 0.00</b> |

**ANNEX B****Bidding Form No. 5****RENOVATION OF DFPC PROVINCIAL STORE OUTLETS - LOT 2 ILOILO  
BILL OF MATERIALS****4. CASHIER COUNTER**

| Material Description                               | Qty.   | U - Cost | Amount        |
|--|--------|----------|---------------|
| 3/4" Thk 4' x 8' Marine Plywood                    | 5 pcs  |          |               |
| 2" x 3" x 10' s4s kd good lumber                   | 5 pcs  |          |               |
| Stickwell  | 1 gal  |          |               |
| drawer guide 16"                                   | 4 pcs  |          |               |
| drawer handle                                      | 2 pcs  |          |               |
| assorted finishing nail                            | 2 kg   |          |               |
| Solid Surface marble white finished                | 6 sq.m |          |               |
| 6mm x 4' x 8' Pure Teakwood laminate machine press | 3 pcs  |          |               |
| Automotive glazing putty                           | 2 gal  |          |               |
| Automotive Lacquer thinner                         | 3 gal  |          |               |
| Automotive Lacquer Paint                           | 1 gal  |          |               |
| Automotive Lacquer Primer                          | 2 gal  |          |               |
| Consumables  | 1 lot  |          |               |
| Polituff w/ hardiner                               | 1 gal  |          |               |
| <b>Total Amount :</b>                              |        |          | <b>P 0.00</b> |

**5. DROP CEILING**

| Material Description                                 | Qty.    | U - Cost | Amount      |
|--|---------|----------|-------------|
| 1" x 2" x 5 m. Metal Furing                          | 30 pcs  |          |             |
| 1" x2 "x 5mtr. Carrying channel                      | 10 pcs  |          |             |
| 1" x 1" x 12' Wall Angle                             | 30 pcs  |          |             |
| Black screw 1 1/2"                                   | 600 pcs |          |             |
| Blind Rivet 1/4" x 5/32                              | 2 box   |          |             |
| 9mm x 4'x 8' Gypsum board                            | 3 pcs   |          |             |
| 6mm x 4' x 8' Pure Teak wood laminate machine press. | 9 pcs   |          |             |
| Consumables  | 1 lot   |          |             |
| <b>Total Amount :</b>                                |         |          | <b>0.00</b> |

**6. STORE FRONT FAÇADE**

| Material Description   | Qty.    | U - Cost | Amount        |
|--|---------|----------|---------------|
| 1/4" Thk.2"x 2" Steel angular  | 8 pcs   |          |               |
| Welding rod  | 4 kg    |          |               |
| Epoxy Primer w/ Cathalist  | 1 gal.  |          |               |
| 3/4" 4' x 8' Phenolic board  | 4 pcs   |          |               |
| Aluminum Composite Panel(copper finish)  | 44 sq.m |          |               |
| Travertine stone   | 9 sq.m  |          |               |
| 1/4" Thk.2" Steel Flat bar   | 2 pcs   |          |               |
| LED Striplight (out door) ; IP20;daylight;1080 lm/m;<br>cri80;4000k color temp | 7 rolls |          |               |
| Bolt & nut 12mm dia.high Tensile Stainless                                     | 50 pcs  |          |               |
| Concrete Epoxy   | 2 gal.  |          |               |
| Scaffolding  | 1 lot   |          |               |
| Consumables  | 1 lot   |          |               |
| <b>Total Amount :</b>  |         |          | <b>P 0.00</b> |

**ANNEX B**  
**Bidding Form No. 5**

**RENOVATION OF DFPC PROVINCIAL STORE OUTLETS - LOT 2 ILOILO**  
**BILL OF MATERIALS**

**7. ELECTRICAL WORKS**

| Material Description                  | Qty.      | U - Cost | Amount        |
|---------------------------------------|-----------|----------|---------------|
| 20 watts-3500K CRI 90 220v(s)         | 23 pcs    |          |               |
| 3.5mm <sup>2</sup> thhn stranded wire | 1 rolls   |          |               |
| EMT pipe ½"                           | 10 length |          |               |
| EMT straight connector                | 15 pcs    |          |               |
| EMT coupling ½"                       | 15 pcs    |          |               |
| 1-36 W LED T5 w/ casing               | 5 pcs     |          |               |
| G. I. Wire # 16                       | 3 kg      |          |               |
| Flexible metal hose 1/2"              | 10 mtrs   |          |               |
| Consumables                           | 1 lot     |          |               |
| <b>Total Amount :</b>                 |           |          | <b>P 0.00</b> |

**SUMMARY**

| Scope of Works  | Amount        |
|---|---------------|
| 1. Painting Works :( Ceiling /Wall ) ,( Hanging Cabinet and Tables) |               |
| 2. Flooring   |               |
| 3. Temporary Enclosure  |               |
| 4. Cashier Counter  |               |
| 5. Drop Ceiling   |               |
| 6. Store Front Façade   |               |
| 7. Electrical Works   |               |
| <b>Total Amount :</b>   |               |
|   | <b>P 0.00</b> |

**LUMPSUM ITEMS**

| Material Description  | Amount        |
|---|---------------|
| 1 Lot tarpaulin 3.0mtrs. X 10 mtrs  |               |
| 1 lot Dismantling existing Store front signages & ACP Cladding / Hauling and disposal   |               |
| 1 lot Stripping of vinyl tiles & disposal   |               |
| 1 lot Dismantling of existing ACCU & ACU  |               |
| <b>1 lot Supply &amp; installation of Inverter Type Aircon units: 1 unit 1.0 HP &amp; 1 unit 2.0 HP Wall Mounted; 1 unit 3 tons Ceiling Casette</b> |               |
| Signages (DUTY FREE PHILIPPINES & ITS MORE FUN IN THE PHILIPPINES ) 2 units   |               |
| 1 lot Supply and installation including preparation of flooring Vinyl Tiles(Store area)   |               |
| <b>Total Amount</b>   |               |
|   | <b>P 0.00</b> |
| <b>GRAND TOTAL</b>  |               |
|   | <b>P 0.00</b> |

**Note:**

DFPC reserves the right to require other materials not listed above, should these be needed in the completion of the entire works. It is the Bidder's responsibility to include in its bid price, the cost of all other materials necessarily included in the works, in accordance with the approved Architectural plans and Specifications.

\_\_\_\_\_  
Signature over printed name

\_\_\_\_\_  
Position

Duly authorized to sign this Bill of Materials for and on behalf of \_\_\_\_\_

Date : \_\_\_\_\_