

## **Project Name: Termite Control Program at Luxe Duty Free**

### **Scope of Work:**

1. Conduct a thorough survey and inspection of the entire area to pinpoint termite infestation
2. Drilling 20mm holes around infested structures and possible termite entry points using a portable automatic roto hammer drill when required .(if possible)
3. Direct slab injection of Fipronil termicide solution using a sub-slab rodder will be initiated. (if possible)
4. Direct soil injection injection of Fipronil termicide solution using a soil rodder or soil injector on the outside perimeter of the building or structure.
5. Installation of Sentricon Above Ground stations(Recruit AG) in identified areas where active termite infestations are present.
6. Monitoring schedule of active stations every 15 days. Additional bait stations will be added if required to ensure successful elimination of termite colonies.
7. Upon achievement of colony elimination, monitoring will be every quarter(3 months) including house inspection.
8. During the monitoring/inspection activities, FMD personnel will be informed of the following:
  - a) Any new or increased termite activity noted in the stations.
  - b) Any addition/removal of recruit termite bait
  - c) Any other findings that will be of concern to property owner with regards to protection of their structure.
9. Mound demolition if any.



**EDGARDO C. ISIDRO**

Manager

Facilities Management Dept.